
ES	EXECUTIVE SUMMARY	ES-1
1.0	INTRODUCTION.....	1-1
1.1	BACKGROUND	1-1
1.2	SUMMARY OF PREVIOUS PHASE 1 PART 1 CSO CONTROL PLAN.....	1-2
1.3	SCOPE OF WORK OF PHASE 1 PART 2 CONTROL PLAN.....	1-4
1.3.1	Field Activities	1-4
1.3.2	Model Evaluation and Selection.....	1-5
1.3.3	GIS Update	1-5
1.3.4	Windshield Surveys and Development of Public Inflow Source Conceptual Separation Plans	1-6
1.4	PHASE 1 PART 2 CSO CONTROL PLAN OBJECTIVES	1-6
2.0	THAMES STREET INTERCEPTOR TELEVISION INSPECTION	2-1
3.0	FLOW ISOLATION AND CCTV INSPECTION.....	3-1
4.0	MANHOLE INSPECTIONS	4-1
5.0	HOUSE TO HOUSE SURVEYS.....	5-1
6.0	SMOKE TESTING	6-1
7.0	DYE TESTING.....	7-1
8.0	CATCHMENT AREA 6 FLOW METERING	8-1
9.0	DATA ANALYSIS FOR INFLOW AND INFILTRATION	9-1
9.1	SUMMARY AND REVIEW OF INFLOW	9-1
9.1.1	Methodology to Estimate Inflow Calculations Contributing to the System from the Inflow Source	9-1
9.1.2	House to House Survey	9-2
9.1.3	Smoke Testing	9-3
9.1.4	Dye Testing.....	9-3
9.1.5	Summary of Inflow	9-4
9.2	SUMMARY AND REVIEW OF INFILTRATION	9-4
9.2.1	Flow Isolation.....	9-5
9.2.2	Manhole Inspections.....	9-5
9.2.3	Summary of Infiltration	9-5
9.3	SUMMARY OF ESTIMATED INFILTRATION AND INFLOW	9-6
10.0	HYDRAULIC MODELING SOFTWARE SELECTION.....	10-1
11.0	GIS UPDATE.....	11-1
12.0	WINDSHIELD SURVEYS	12-1
13.0	UPDATE OF CSO REDUCTION AND CONTROL ALTERNATIVES.....	13-1

13.1	CSO CONTROL ALTERNATIVES	13-1
13.1.1	Nine Minimum Controls and Best Management Practices	13-1
13.1.2	Enhanced Sewer Separation	13-1
13.1.3	Storage/Treatment.....	13-2
13.1.4	Storage, Conveyance and Treatment at the WPCP.....	13-3
13.2	EVALUATION OF CSO ACTIVITY 1998 – 2006.....	13-3
13.3	ESTIMATES OF CSO REDUCTION.....	13-10
14.0	CONCLUSIONS AND RECOMMENDATIONS.....	14-1
14.1	CONCLUSIONS	14-1
14.2	RECOMMENDATIONS	14-9
	14.2.1 Phase 1 Part 3 CSO Control Plan Scope of Services, Cost and Implementation Schedule	
		14-9
	14.2.2 Phase 2 CSO Control Plan Scope of Work, Cost, and Implementation Schedule ...	14-11
14.3	OVERALL CSO CONTROL PLAN SCHEDULE AND COSTS	14-15

APPENDIX A (Under Separate Cover)

Volume 1 of 7

Thames Street Television Inspection Report, March 2006

Flow Isolation Report, April 2006

Instantaneous Flow Measurement Report, June 2006

Television Inspection Report, May-September 2006

Volume 2 of 7

Manhole Inspection Report, January 2005

Manhole Inspection Report, March-May 2006

Volume 3 of 7

Building Inspection Report, Sub Area 1

Volume 4 of 7

Building Inspection Report, Sub Area 3

Volume 5 of 7

Building Inspection Report, Sub Area 4

Volume 6 of 7

Smoke Testing Report, July 2006

Dye Testing Report, September-December 2006

Flow Monitoring Report, April-May 2006

EPA CSO Policy

RIDEM CSO Policy

Volume 7 of 7

GIS Manhole Inspection Report (Draft Manhole Inspection Forms – Final report to be submitted upon receipt)

LIST OF TABLES

TABLE ES.1	SUMMARY OF SEWER SYSTEM EVALUATION SURVEY RESULTS	ES-5
TABLE ES.2	PHASE 1 PART 3 CSO CONTROL PLAN COST	ES-7
TABLE ES.3	PHASE 2 CSO CONTROL PLAN COST ESTIMATE	ES-13
TABLE 9.1	SUMMARY OF ESTIMATED INFLOW PRIORITY CATCHMENTS 1, 3, AND 4.....	9-4
TABLE 9.2	SUMMARY OF ESTIMATED INFILTRATION PRIORITY CATCHMENTS 1, 3, 4 AND 7.....	9-6
TABLE 9.3	SUMMARY OF ESTIMATED INFILTRATION AND INFLOW PRIORITY CATCHMENTS 1, 3, 4 AND 7.....	9-6
TABLE 12.1	CONCEPTUAL CATCH BASIN SEPARATION CRITERIA.....	12-5
TABLE 13.1	SUMMARY OF CSO EVENT DATA 1998 - 2006.....	13-3
TABLE 13.2	CSO ACTIVITY SUMMARY 1998 - 2006.....	13-4
TABLE 13.3	WELLINGTON AVENUE CSO FACILITY CSO DISCHARGES 1998 – 2006 (CHRONOLOGICAL)	13-5
TABLE 13.4	WELLINGTON AVENUE CSO FACILITY CSO DISCHARGES 1998 – 2006 (BY CSO VOLUME).....	13-6
TABLE 13.5	ANNUAL CSO EVENTS, ASSOCIATED RAINFALL AND VOLUMETRIC COMPARISONS 1998 – 2006	13-7
TABLE 13.6	ESTIMATED VOLUMES FOR CSO EVENT REDUCTION AT THE WELLINGTON AVENUE CSO FACILITY	13-10
TABLE 14.1	SUMMARY OF SEWER SYSTEM EVALUATION SURVEY RESULTS AND RECOMMENDATIONS PRIORITY CATCHMENTS 1, 3, 4 AND 7.....	14-3
TABLE 14.2	PHASE 1 PART 3 CSO CONTROL PLAN COST	14-10
TABLE 14.3	PHASE 2 CSO CONTROL PLAN COST ESTIMATE	14-13
TABLE 14.4	OVERALL CSO PROGRAM COSTS FOR RECOMMENDED IMPROVEMENTS.....	14-18

LIST OF FIGURES

FIGURE ES.1 WELLINGTON AVENUE CSO TREATMENT FACILITY TRIBUTARY
CATCHMENTS ES-2

FIGURE ES.2 PHASE 1 PART 3 CONTROL PLAN FOR COMBINED SEWER OVERFLOWS PROJECT
IMPLEMENTATION SCHEDULE..... ES-8

FIGURE ES.3 PHASE 2 CONTROL PLAN FOR COMBINED SEWER OVERFLOWS PROJECT
IMPLEMENTATION SCHEDULE..... ES-14

FIGURE 1.1 WELLINGTON AVENUE CSO TREATMENT FACILITY TRIBUTARY
CATCHMENTS 1-3

FIGURE 11.1 INSPECTED MANHOLE LOCATIONS 11-2

FIGURE 12.1 CATCH BASIN SEPARATION 12-3

FIGURE 13.1 WELLINGTON AVENUE CSO FACILITY DISCHARGES-JANUARY 1998 THROUGH
APRIL 2005..... 13-9

FIGURE 13.2 WELLINGTON AVENUE CSO FACILITY DISCHARGES JANUARY 1998 THROUGH
APRIL 2006..... 13-9

FIGURE 14.1 PHASE 1 PART 3 CONTROL PLAN FOR COMBINED SEWER OVERFLOWS PROJECT
IMPLEMENTATION SCHEDULE 14-10

FIGURE 14.2 PHASE 2 CONTROL PLAN FOR COMBINED SEWER OVERFLOWS PROJECT
IMPLEMENTATION SCHEDULE 14-14

FIGURE 14.3 OVERALL CSO CONTROL PLAN SCHEDULE 14-16